



धनगढी उप-महानगरपालिका



नगर कार्यपालिकाको कार्यालय

धनगढी, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल |

दररेट पेश गर्ने सम्बन्धी सूचना


प्रकाशित मिति: २०७९/१०/१२

१. धनगढी उप-महानगरपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपसिल बमोजिमको कार्य गर्नका लागि दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ।

क्र. स.	विवरण	जम्मा रकम (मु. अ. क. बाहेक)	दररेट पेश गर्ने अन्तिम समय	कैफियत
1	Construction Of Motorcycle Parking Place at Dhangadhi Sub-metropolitan Ward 5 Office	3,96,252/76	(2 nd Feb 2023) 2079/10/18 B.S. 05:00 PM	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपि, नवीकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजतपत्र) प्रमाणपत्रको प्रतिलिपि, मु. अ. क. दर्ता प्रमाणपत्रको प्रतिलिपि र आ. व. २०७८/०७९ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्ने छ।
३. उक्त कार्यको लागि आवश्यक BoQ यस कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
४. BoQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ। केरमेट भएको दररेट (BoQ) मुल्यांकनमा समाबेस गरिने छैन।

प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत



Dhangadhi Sub-Metropolitan City

Bill of Quantities

Name of Works: Construction Of Motorcycle Parking Place at Dhangadhi Sub-metropolitan Ward 5 Office

S.N.	Description of Works	Unit	Quantity	Rate(NRs)		Amount (NRs.)
				In figure	In words	
1	Earth work excavation in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per the instruction of site engineer.	Cum	2.94			
2	Earth work back filling & also new Earth filling in foundation, trenches (Earth transported from 10 m. surrounding) work in every 15-15 cm. layer with watering & proper manual compaction (except earth rate) as per the instruction of site engineer.	Cum	14.88			
3	Supply & Filling Rubble stone with line and levelled work in foundation .	Cum	1.40			
4	Plain cement Concrete (PCC) in 1:2:4 ratio for foundations, flooring and walls with approved quality of cement, sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	Cum	3.33			
5	Fabricating, supplying & fixing of different size M.S. black pipe Truss with metal primer as per specification and instruction.	kg	431.00			
6	Supplying & Fitting 2 mm Thick UPVC sheet with all complete accessories	Sqm	46.75			
7	Providing and laying 50 mm thick Interlocking concrete block with 50 mm thick Crushed stone chip as per specification and instruction of site engineer.	Sqm	49.60			
Total Bidding amount in Nrs.						
			VAT @13%			
Total Including VAT						

Total In Words:

Stamp of Firm/ Company and Signature of Authorized Person: