



# धनगढी उप-महानगरपालिका

१३ नं. वडा कार्यालय

धनगढी कैलाली

सुदूरपश्चिम प्रदेश नेपाल



प.स. : २०८१/०८२

च.न. :


## दररेट पेश गर्ने सम्बन्धि सूचना

प्रथम पटक प्रकाशित मिति: २०८१/१०/२८

१. धनगढी उप-महानगरपालिका वडा नं. -१३ द्वारा विभिन्न निर्माण व्यवसायी संग तपसिल बमोजिमको निर्माण कार्य गर्नका लागि दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ ।

क्र.स.	विवरण	जम्मा रकम (मू.अ.क.) सहित	दररेट पेश गर्ने अन्तिम समय	कैफियत
१.	धनगढी उप-महानगरपालिका वडा नं. १३, कैलाली गाउँ जनता राष्ट्रिय मा.वि.को इयाल ढोका र प्लास्टर	२,९९,५९७.१५	२०८१/११/०४ B.S. 5:00 PM(कार्यालय समय भित्र)	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रुपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको निवेदन सहित फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपि , व्यवसाय दर्ता (निर्माण व्यवसायी इजाजतपत्र ) प्रमाणपत्रको प्रतिलिपि , मू.अ.क. दर्ता प्रमाणपत्रको प्रतिलिपि र आ.व. २०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरी पेश गर्नुपर्ने छ ।
३. उक्त कार्यका लागि आवश्यक BOQ धनगढी उप-महानगरपालिका नगरकार्यापालिका कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिने छ ।
४. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पस्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ । केरमेट भएको दररेट (BOQ) मूल्याङ्कनमा समावेश गरिने छैन ।

  
अम्बा दत्त भट्ट  
वडा सचिव  
वडा सचिव  
ध.उ.म.न.पा.वडा नं.१३





धनगढी उपमहानगरपालिका  
नगर कार्यपालिकाको कार्यालय  
धनगढी, कैलाली, सुदूरपश्चिम प्रदेश, नेपाल

**BILL OF QUANTITIES**

वडा सचिव  
धनगढी उप-महानगरपालिका  
१३ नं. वडा कार्यालय  
कैलाली, कैलाली  
सुदूरपश्चिम प्रदेश, नेपाल

Project: Construction of Door and Plaster of Janta Rastriya Ma. Vi. School  
Location: Ward No. 13 Kailali Gau.

S.N.	DESCRIPTION OF WORKS	UNIT	Quantity	RATE(Without VAT in NRs)	Rate in words (Without VAT in NRs)	REMARKS
<b>A</b>	<b>CIVIL WORKS</b>					
1	Good quality local chimney made Brickwork in 1:4 C/S mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	m <sup>3</sup>	3.81			
2	Net Cement Punning works over the Screeding works including necessary curing all complete as per the instruction.	m <sup>2</sup>	88.55			
3	12.5 mm thick cement sand plaster work (1:4) including supply of materials, labor, mixing, levelling, curing & scaffolding etc. all complete as per drawing, specification.	m <sup>2</sup>	234.35			
4	Supplying & applying Two coat Emulsion Paint of approved colour with primer painting over properly cleaned surface at plastered surface all complete as per approved drawing, Specification and instruction of site engineer.	m <sup>2</sup>	322.90			
<b>B</b>	<b>ELECTRICAL WORKS</b>					
1	Wiring for light point/ exhaust fan/ call bell point with 1.5 Sq.mm PVC insulated, copper conductor cable for lighting and 4 sq. mm pvc insulated copper conductor cable for power point in surface/ recessed steel conduits along with 1 No. 2.24 mm dia. bare copper wire for loop earthing including 6 Amp modular type switch, modular cover plate and suitable M.S. Box complete as required Dyna/CPL.	Point	10.00			
2	Distribution board 6 way DB made of mild steel sheet double cover push lock size flush type, etc all complete	Nos.	1.00			
3	16A SP MCB	Nos.	2.00			
				(A) Total Amount		
				(B) VAT @ 13%		
				Grand Total (A+B)		
	Grand Total (A+B) Amounts in words:					

Name Of The Firm:

Signature Of Authorized Person:

Seal Of Firm:

Date: