

Dhangadhi Sub Metropolitan City

Office of Municipal Executive

Dhangadhi, Kailali

BILL OF QUANTITIES

प्रमुख प्रशासकीय अधिकृत

Name of Work :- Construction of Retaining Wall and Pit at ward 16/18 gausala.

S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
1	Excavation of all type of soils including disposal (Upto 10m lead & 1.5m lift.).	Cum	64.00				
2	Providing and soling stone in true line and level including filling of voids by local sand all complete as per drawing, specification.	Cum	10.20				
3	75 mm thick Plain cement concrete work in ratio of 1:2:4 cement:sand: coarse aggregate on foundation bed including mixing, laying, compacting and curing of works all complete as per drawing, specification.	Cum	5.10				

12/1

Name of Work :- Construction of Retaining Wall and Pit at ward 16/18 gausala.

S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
4	Providing and Laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications) 60% M15 Concrete and 40% Boulders/stones using Mechanical aids.	Cum	40.54				
5	Supplying, Providing and Laying 75 mm HDPE pipe	Kg	32.56				
				Sub Total Rs.			
				VAT @ 13%			
				Grand Total NRs.			

Name of Firm:

Address:

Signature:

Date:

Seal: