



धनगढी उप-महानगरपालिका

११ नं. वडा कार्यालय

घोडसुवा, धनगढी, कैलाली

सुदूरपश्चिम प्रदेश नैपाल



दररेट पेश गर्ने सम्बन्धी सूचना

प्रकाशित मिति: २०८२/०१/२४

१. धनगढी उप-महानगरपालिका वडा नं. -११ को स्वीकृत बार्षिक कार्यक्रम अनुसार तपसिल बमोजिमको कार्य शिलबन्दी दरभाउ पत्र मार्फत गर्नु पर्ने भएकाले इच्छुक फर्म/सप्लायर्सले यो सूचना प्रकाशित भएको मितिले ७ दिन भित्र शिल बन्दी दरभाउ पत्र धनगढी उप-महानगरपालिका ११ नं. वडा कार्यालयमा पेश गर्न हुन यो सूचना प्रकाशित गरिएको छ ।

क्र.स.	विवरण	जम्मा रकम (मु.अ.क.) बाहेक	दररेट पेश गर्ने अन्तिम समय	कैफियत
१.	धनगढी उप-महानगरपालिका - ११, बेलादेवीपुर धामको रिंगरोडमा पक्कि नाली निर्माण गर्ने काम	८,३४,९१९/४०।-	वि. सं. २०८२/०१/३० (13 th May, 2025) (कार्यालय समय भित्र)	

२. दररेट पेश गर्ने फर्म/सप्लायर्सले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/ कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी , मु.अ.क. दर्ता प्रमाणपत्रको प्रतिलिपी र आ.व. २०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरी पेश गर्नुपर्ने छ ।
३. उक्त कार्यका लागि आवश्यक BOQ फारामयस धनगढी उप-महानगरपालिका कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिने छ ।
४. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ । अंक र अक्षरमा फरक पर्न गएमा अक्षरलाई मान्यता दिइनेछ । केरमेट भएको दररेट (BOQ) मूल्याङ्कनमा समावेश गरिने छैन ।

सीता कुमारी के.सि
वडा सचिव
वडा सचिव

Dhangadhi Sub-Metropolitan City

Office of ward-11

Dhangadhi, Kailali



धनगढी उप-महानगरपालिका
११ नं. वडा कार्यालय

वडा सचिव

Name of project: धनगढी उप-महानगरपालिका - ११, बेलादेवीपुर धामको रिंग रोडमा पक्कि नाली निर्माण

Location: Dhangadhi-11, Kailali

Contract ID:

S. N.	Particulars	Unit	Quantity	Rate		Amount	Remarks
				In Figure	In words		
1	Roadway excavation in all types of soil/rock by both manual and mechanical means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer.	Cu.m	45.43				
2	Providing and laying of hand pack Stone soling with 150 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cu.m	11.51				
3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.	Cu.m	7.67				
4	Plain cement Concrete (PCC) for RCC works (1:1.5:3) for slab/lintels with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	Cu.m	23.25				
5	8 mm Dia Reinforcement bar of fe 500 grade including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing, Specification and instruction of site engineer.	Kg	1904.02				

Dhangadhi Sub-Metropolitan City

Office of ward-11

Dhangadhi, Kailali

2013/11/11
वडा सचिव

Name of project: धनगढी उप-महानगरपालिका - ११, बेलादेवीपुर धामको रिग रोडमा पक्क नाली निर्माणको काम

Location: Dhangadhi-11, Kailali

Contract ID:

११ नं. वडा कार्यालय
धनगढी, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल

S. N.	Particulars	Unit	Quantity	Rate		Amount	Remarks
				In Figure	In words		
6	Formwork for RCC and PCC Works (width of wooden planks should not be greater than 100 mm).	Sq.m	325.09				
7	Supply and Installation of Project Information Board (Using Iron Sheet, Frame and Pole)	Nos.	1.00				
Total							
VAT							
Total Cost with VAT							

Total in Words:

Name of firm/company:

Address:

Signature:

Stamp: