



धनगढी उप-महानगरपालिका



नगर कार्यपालिकाको कार्यालय

धनगढी, कैलाली
सुदूरपश्चिम प्रदेश, नेपाल

दररेट पेश गर्ने सम्बन्धी सूचना

प्रकाशित मिति: २०८१/०१/१२

१. धनगढी उप-महानगरपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपसिल बमोजिमको कार्य गर्नका लागि दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ।

क्र. स.	विवरण	जम्मा रकम (मु. अ. क. बाहेक)	दररेट पेश गर्ने अन्तिम समय	कैफियत
१	धनगढी उप-महानगरपालिका १२, चौतारो निर्माण गर्ने काम	२,७९,८९४.३७/-	(Apr. 30 th 2024) २०८१/०१/१८ कार्यालय समय भित्र	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रुपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपि, नवीकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजतपत्र) प्रमाणपत्रको प्रतिलिपि, मु. अ. क. दर्ता प्रमाणपत्रको प्रतिलिपि र आ. व. २०७९/०८० को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्ने छ।
३. उक्त कार्यको लागि आवश्यक BoQ यस कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
४. BoQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ। केरमेट भएको दररेट (BoQ) मुल्यांकनमा समावेश गरिने छैन।

.....
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

Dhangadhi Sub Metropolitan City
Office of Municipal Executive
Dhangadhi, Kailali
BILL OF QUANTITIES

परियोजनाको नाम :- चौतारो निर्माण गर्ने काम

कार्यान्वयन हुने स्थल : धनगढी उप-महानगरपालिका - १२, ए गाउँ डाडा पिपल चौतारो

Chief Administrative Officer

S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
1	Excavation in Ordinary Soil for foundation of structure including removal and satisfactory disposal of all materials up to a lead of 10m and 1.5m Lift as instructed by Engineer.	cu.m	28.01				
2	Plain cement Concrete (PCC) in 1:2:4 ratio for foundations and flooring with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc all complete as per appro	cu.m	1.35				
3	Form work for Foundation, beams, column, slab etc. all types of concrete with 19 mm plyboard with steel props centering & shuttering including prompting wedging, scaffolding, propping, staging inclusive of utilization till the support is fully unyielding net as per design ,drawing specification and instruction	sq.m	41.88				

परियोजनाको नाम :- चौतारो निर्माण गर्ने काम

कार्यान्वयन हुने स्थल : धनगढी उप-महानगरपालिका - १२, ए गाउँ डाडा पिपल चौतारो



S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
4	RCC work: RCC work in PCC (1:1.5:3) in foundation, floors, columns, beams, slabs etc. with cement,sand and crussed aggregate of 10 mm to 38mm gauge including mixing with mixture machine & compaction by vibrator, laying in line & level with curing all type of works complete as per specifications & instructions	cu.m	6.19				
5	Tor /TMT Reinforcement work for R.C.C work including supply, straightening, cutting, bending, binding and laying of different diameter steel rod in all types of R.C.C, 12 mm	kg.	486.40				
6	Tor /TMT Reinforcement work for R.C.C work including supply, straightening, cutting, bending, binding and laying of different diameter steel rod in all types of R.C.C, 8 mm	kg.	55.62				
7	First class local chimney made brick wall work in cement sand mortar (1:4) in perfect line and level including wetting the brick, packing the joints and curing all types of works as per specification and instruction by Engineer (fair faced brick work)	cu.m	3.00				

परियोजनाको नाम :- चौतारो निर्माण गर्ने काम

कार्यान्वयन हुने स्थल : धनगढी उप-महानगरपालिका - १२, ए गाउँ डाडा पिपल चौतारो



S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
8	Supplying and Laying of 12.5mm thick cement sand plaster in (1:4) ratio on ceiling of good finish including supply of materials, racking the joint, wetting of surfaces & curing the work at least 7days all complete as per approved drawing, Specification a	sq.m	19.25				
9	Earth work in filling in foundation, floors etc in 15 cms layers and compaction by water spray all complete	cu.m	14.72				
Sub Total Rs.							
VAT @ 13%							
Grand Total NRs.							

Name of Firm:

Address:

Signature:

Date:

Seal: